

# 2015 Bridge Workers and Supervisors Conference


County Bridge Program and Panel Discussion

# Clinton County Engineer


Jeffrey B. Linkous P.E.,P.S.




# Clinton County Stats

- ▶ Population:
    - County – 42,040
    - City of Wilmington – 12,520
  - ▶ 265 Miles of County roads
  - ▶ 299 Miles of Township roads
  - ▶ 295 Bridges
  - ▶ 1042 Culverts
- 


# Employees

- ▶ 25 Highway Workers
    - 3 Mechanic/Maintenance
    - 1 Grounds
    - 1 Sign Department
    - 20 Crew members
  - ▶ 8 Office Staff
    - 2 Highway Department
    - 6 Engineers Office
  - ▶ 2 Tax Map Office
  - ▶ 1 GIS Department Manager
  
  - ▶ 36 Total Employees
- 


# Bridge Replacements

- ▶ 295 Total Bridges that we are responsible for on County and Township roads
  - ▶ Started effort to upgrade bridges in 1974
  - ▶ Completed 248 Full Replacements
  - ▶ 28 Major Rehabilitations
  - ▶ 276 bridges rehabilitated or replaced since 1975
- 


# Types of bridges

- ▶ 5 Concrete Slabs
  - ▶ 124 Precast Concrete Boxes
  - ▶ 8 Concrete Pipe or Arch
  - ▶ 113 Prestressed Box Beam Bridges
  - ▶ 11 Steel Beam or Girder
  - ▶ 23 Steel Multi Plates and Pipes
  - ▶ 3 Stone Arches
  - ▶ 5 Aluminum Pipe or Arches
  - ▶ 3 Trusses
- 

# Progression of Construction


- ▶ 1970's and Early 1980's Steel Beam on concrete abutments
  - ▶ 1981 Began using prestressed box beams
  - ▶ 1983 Multi Plate Pipes
  - ▶ 1986 Concrete Boxes
  - ▶ 2004 Fiber Reinforced polymer deck
  - ▶ 2009 Prestressed beams with composite deck
- 

# Steel Beam Bridges

- ▶ In 1975 Ceasars Creek Lake was being constructed in Warren and Clinton County
  - ▶ State Bridges were torn out
  - ▶ County was able to obtain old steel beams at scrap prices
  - ▶ Brought to our property
  - ▶ Had local bridge company cut to our required length
  - ▶ Sand blasted and painted
- 



# Steel Beam Bridges (cont)

- ▶ Local bridge company began building abutments and then trained our crews
  - ▶ Built cantilever walls with spread footings
  - ▶ Simple plans
  - ▶ Corrugated steel deck
  - ▶ Paved asphalt deck
- 

# Salvaged Beams




Mills Road




Ireland Road

# Basic Plans



# Prestressed Box Beams

- ▶ 1981 we began using prestressed box beam bridges.
  - ▶ Similar footer and abutment design as steel beam
  - ▶ Our crews did all road work and poured abutments
  - ▶ Prestressed beams delivered and set
  - ▶ County crews fill joints and waterproof
  - ▶ Asphalt surface
- 



# Formwork



2 foot thick walls on  
spread footers



Plywood forms



Waterproofing



Widen Approaches



# Completed Bridge




Hunter Road



Hunter Road

# Multi-Plate Pipes


- ▶ Needed solution for spans in the 10–16 foot in length
  - ▶ Low profile, replacing steel beam bridges
  - ▶ Low volume roads
  - ▶ Used multi-plate Arches and Pipe Arches
  - ▶ County crews prepared site and poured footers for arches.
  - ▶ Put together and bolted all plates
  - ▶ Backfill was critical
- 



# Multi-Plate Arch




Arch with gabion  
headwalls




Concrete footers

# Plans !





Concrete footer design



Basic plans




# Manufacturers Plans




## Manufacturers plans on panels and bolt locations

# Steel Channel design


# Precast Concrete Boxes

- ▶ 1985 Visited Greene County Engineers Office
  - ▶ They were fabricating concrete boxes based on design by consulting firm: Lockwood, Jones and Beals .
  - ▶ Early design had angled corners for ease of forming
  - ▶ The design was eventually refined and became known as a Consplan
- 

# Precast Concrete Boxes

- ▶ Used existing plans with some modification
  - ▶ Set up “Culvert” shop in an old Lean-to of a building we weren’t using.
  - ▶ Installed furnace
  - ▶ Poured Concrete Pads to build boxes on.
  - ▶ Modified building roof to accommodate removal of boxes with crane
  - ▶ Set-up shop with new rebar bender and cut-off saw
- 

# Precast Plans



# Precast Production Site



► Location Choices



# Removing Culverts



Retrofitted roof



Limited Space



# Stockpiled Boxes



Used old trailer to move  
around yard



Stockpile in yard

# Updated facility 1994





# Production of Culverts



Symons Forms











